

								1				
UPS Rating	kVA	50	70	100	140	150	200	210	250	280	350	
	kW	50	70	100	140	150	200	210	250	280	350	
Voltage	Input	480	480	480	480	480	480	480	480	480	480	
	Output	480	480	480	480	480	480	480	480	480	480	
AC Rectifier Input (A)	Nom	62	87	124	174	187	250	262	311	349	436	
	Max	73	98	146	196	220	294	295	366	393	491	
	Rec OCPD	80	125	175	250	250	350	350	400	500	600	
AC Bypass Input (A)	Nom	60	84	120	168	180	241	253	300	337	421	
	Max	60	84	120	168	180	241	253	300	337	421	
	Rec OCPD	80	125	150	250	250	300	350	400	500	600	
Battery	Nominal VDC	+/- 240	+/- 240	+/- 240	+/- 240	+/- 240	+/- 240	+/- 240	+/- 240	+/- 240	+/- 240	
	Average DC Current	110	154	220	309	331	441	463	551	617	772	
	Max DC Current	132	185	265	370	397	529	556	662	741	926	
AC Output (A)	Nom	60	84	120	168	180	241	253	300	337	421	
	Rec OCPD	80	125	150	250	250	300	350	400	500	600	
Max BTU @ Full Load	BTU/Hr	6186	8863	12376	17323	18562	24745	25986	30937	34650	43313	
Dimensions (UPS only)	Inches (mm)	31.5W x 42"D x 78.7"H (546W x 1067W x 2000H)										
Approx Weight of UPS	lbs (kg)	891 (404)	891 (404)	995 (451)	995 (451)	1099 (498)	1203 (546)	1099 (498)	1307 (593)	1203 (546)	1307 (593)	

Notes:

- 1) Manufacturer recommends sizing all cables and overcurrent protection for maximum kVA of the UPS cabinet being installed to allow for future expansion.
- 2) UPS must be installed in accordance with all local, state and national electrical codes.
- 3) Ground conductor to be sized per NFPA 70 250.66.
- 4) Max currents are based on nominal current plus max battery charge current and are not considered continuous per NEC code.
- 5) DC current listed is average DC current.

XTREME		CT X90-5S					
		X90-5S One-Line Preliminary					
APPROVED	SIZE	CODE		DWG NO		REV	
CHECKED	Α			X90-5S-OND-480-480		3	
DRAWN JB 7/2/2021	SCALE	1:1	WE	IGHT	SHEET 2/2		